



## ENPAC, LLC CERTIFICATION NOTICE

July 30, 2018

**NOTICE NO#:** 3280-6012

**PRODUCT:** Mini Stacker (ENPAC Part No#. 6012- Standard colors)

**MANUFACTURER AND TESTING FACILITY:** ENPAC, LLC., 34355 MELINZ PARKWAY, EASTLAKE OHIO 44095

**SERIAL NUMBER OF UNIT TESTED:** 3-1-032118

**REGULATION:** ENPAC Regulated Static Load Test.

**OBJECTIVE:** To determine the compliance to ENPAC's Load standard set for this product.

**ITEM TESTED:** One (1) sample of the Mini Stacker. Material of construction is high density polyethylene (HDPE) rotationally molded.

TEST	DESCRIPTION
Hot Box Load Test	Load capacity must meet or exceed 100.0 lbs./ 45.3 kg UDL (Uniformly Distributed Load) @ 120°±5°F/49°±3°C for 100 Hours.

**CONCLUSION:** Part design complies and meets required testing as called out above. This unit is ENPAC Certified with a UDL (Uniformly Distributed Load) 2 years after the date listed above.

Failure to have a Uniformly Distributed Load renders this qualification invalid and voids all warranties implied or stated.

**LOAD TEST:** ENPAC Certified thru July 30, 2020

100.0 pounds (45.3 kg) Load capacity

Load measured by ENPAC's Filing Scale model Sterling-DW800-N12. Calibrated 05-18. Temperature documented by a Dickson 4" Temperature Recorder. Calibrated 01-18.

**APPROVED BY:**

  
(MANAGING MEMBER)

  
(QUALITY ASSURANCE MANAGER)

DOC:D1009\_05

FILE: D1009\_05.XLS

ECN:4211

REV:05

BY:KH

DATE: 10/10/2013